



Typical RemotePro[®] Installation

Scott Parsons



Typical RemotePro® Installation



TPW-400DT-12/24 BreezePro®
Wind Turbine

RPSTL24-200-320 RemotePro®
System supporting up to 80W

Typical RemotePro® Installation



Bill Of Materials

Qty 1: 36" x 1½" Schedule 40 Galvanized Steel Pipe, 1 end threaded

Qty 1: 3" x 1½" Galvanized Steel Coupling

Qty 1: 15' x 3" Schedule 40 Galvanized Steel Pipe, 1 end threaded

Qty 2: Bags of Cement

Qty 1: Bag Pea Gravel

Notes:

1. A good rule of thumb is 1' below ground for every 5' above ground.

